



C WOOD & SON  
LUTON LTD

# Case Study

**New Driveway  
Luton**

# The Job

C Wood and Son were employed to undertake a driveway project in Luton.

For this project we:

- Lifted the existing block paving and dispose of.
- To remove the concrete edgings and 2No bushes.
- To dig out shingle area.
- To lay MOT and consolidate (shingled area only).
- To install edgings to front and left side of the drive.
- To install aco drain to the rear of the drive.
- To lay 50mm sand and consolidate (shingled area only).
- To level complete drive ready for new blocks.
- To lay charcoal block around the perimeter.
- To lay grey blocks top drive.
- To silver sand and vibrate.

This project was completed in 4 days.













