



C WOOD & SON
LUTON LTD

Case Study



Kitchen Refurbishment
Luton

The Job

C. Wood & Son were employed by a client in Luton to undertake a kitchen refurbishment at their property.



- Opened up to check for steel above arches
- Stripped out the kitchen, hacked off tiles and lifted the flooring
- Removed the ceiling in kitchen and dining room
- Removed the back door and window
- Removed the brickwork to centralise door and bricked up to form new opening.
- Supported the wall, removed the internal arch wall and installed steel
- Installed drainage for new layout - WC, basin and washing machine
- Installed new UPVC back door
- Installed new 3no UPVC windows
- Plied the floor
- Moved the boiler and altered the pipework to suit new layout
- Installed new radiator
- Installed studwork to form utility and WC, insulated and plaster boarded
- To plasterboard and skim ceilings
- Skimmed all the walls
- Tiled the floor
- Installed 2no internal doors and frames
- Installed kitchen and utility
- Tiled splash back to worktops
- Installed 4no shelves to under stair cupboard
- Supplied and installed WC and basin

Continued...

The Job

- Installed electrics:
 - 10no double sockets
 - 5no spurs
 - 5no single sockets
 - 8no downlights with two way switch
 - 2no downlights with two way switch
 - 2no downlights with switch
 - 2no fans
 - 1no cooker point
- Installed skirting
- Primed, applied undercoat and gloss to woodwork
- Applied 1no mist coat and 2no coats of emulsion to walls and ceiling



This project was completed within 8 weeks and our client was over the moon with the end result, as were we.

Great workmanship as always from our tradesmen.











