



C WOOD & SON
LUTON LTD

Case Study



**Kitchen/Diner Refurbishment
Flitwick, Bedfordshire**

The Job

C. Wood & Son were employed by a family in Flitwick, Bedfordshire to carry out a kitchen/diner refurbishment at their family home.



For this project we:

- Protected the doors and staircase with sheeting.
- Stripped out the existing kitchen and dining room
- Took down the ceilings in the kitchen and dining room
- Lifted the floor coverings in the kitchen and dining room
- Installed across props to ceiling joists - letting us knock out the joining wall
- Installed Padstones and steels either end of where the wall was removed
- Removed the back door, tooled out the brickwork and blocked up that door opening with brick cavity and blockwork
- Installed all the electrics
- Disconnected the radiator on the existing wall, altered the pipework for a new radiator in the dining room and altered pipework for a new sink, washing machine, dishwasher and fridge
- Installed new plasterboard to steel and ceiling to complete the new room
- Skimmed all the walls, latexed the floor and installed new flooring to kitchen, diner, hallway and WC
- Installed the new kitchen, new skirtings and tiled the splashback
- Completed decoration of the walls and ceilings with mist coats and emulsion, plus the woodwork.

This project was completed in 6 weeks (not including the 2 week break for Christmas).









