

C WOOD & SON LUTON LTD

> Case Study



## The Job

C. Wood & Son were employed by the Exchange Shopping Centre in Ilford build a Kiosk for the outside section of their centre.

For this project we:

- Erected timber hoarding
- Steel/timber hoarding
- Installed Metsec stud walling, insulated, plied and hardie backer boarded internally
- Install Metsec/timber roof joists
- Installed 50mm insulation to roof
- Plied floor and roof
- Installed sedum roof system
- Installed Corten steel cladding to plinth, opening apertures and doors
- Installed brick slip cladding, 2No doors and 2No serving hatches
- Installed glazed corner panel
- Installed double plasterboard and skimmed internal walls and ceiling
- Installed 2No stop cocks, 2No soil pipe connections, terminated with durgo valve into kiosk from existing cover
- Installed all electrics such as plugs, consumer units, spurs, etc
- Installed door control by Zada
- Installed 2No signs/light boxes and 2No menu boxes
- Carried out decoration by coats of mist and emulsion to walls and ceiling, as well as anti graffiti coating to the external

This was one of our biggest projects to date and the team were over the moon with their work.

The Kiosk is up and running at the time of this PDF.

































































