



C WOOD & SON  
LUTON LTD

# Case Study



**Adaptation & Wetroom  
Luton, Bedfordshire**

# The Job

C. Wood & Son were employed by Luton Borough Council, to undertake an adaptation project for a family in Luton, Bedfordshire.



Unfortunately, whilst undertaking the works, we stumbled upon some asbestos plasterboard and AIB ceiling panels, which we had to quickly remove before proceeding with further building works.

For this project we:

- Stripped out the shower room, internal glass doors and disposed of
- Knocked down the existing shower room walls, dug the trench and installed underground drainage
- Removed asbestos plasterboard and AIB ceiling panels to the ground floor entrance lobby and WC.
- Carried out an air test to the property and disposed of the asbestos waste at a licensed waste disposal site.
- Built stud wall to form new shower room and skimmed
- Installed 2No doors frames and a composite front door with level threshold
- 1st fixed all plumbing and electrics
- Fitted a Tuff form shower tray and 2D light fitting
- Latexed the floor and installed new Altro Aquarius flooring
- Installed basin, pedestal and clos-o-mat WC
- Installed new electric shower, fan and towel rail
- Hung up the shower curtain and installed hand & grab rails
- Install garage unit and surge protection

The family are delighted at the final finished and were so thankfully at how much this adaptation will make a difference to their say-to-day lives.























