



C WOOD & SON
LUTON LTD

Case Study



**External Ramp
Dunstable, Bedfordshire**

The Job

C. Wood & Son were, once again, employed by Queensbury Academy, Dunstable to undertake their external ramp project during the Summer holidays.



We have previously quoted for these works earlier in the year but the school application for funding took a while to come in, so we were very pleased they'd selected us for the works after many months without communication.

For this project we:

- Took down the existing timber ramp, ply panel and disposed of
- Dug footing for brickwork to form ramp and concreted the footings
- Built 9" brick walls to form a "Zig Zag" ramp
- Installed brick on edge coping
- Laid MOT type 1 and consolidated
- Laid sand bed, consolidated and levelled out
- Laid Slabs to form the ramp and level area
- Installed steel post for the disabled door push button (button was installed by others)
- Installed kee klamp handrails
- Made good of the soffit board where the ply barrier was removed
- Cleared site on completion

We were up against the clock for this project, with it being during the Summer holidays. But we had this completed in under 3 weeks, right on schedule.

School board are happy and the ramp is proving to be a great addition to the school facilities.













