



C WOOD & SON
LUTON LTD

Case Study

Plaster & Render
Sheffield



The Job

C. Wood & Son were employed by a couple in Shefford, Central Bedfordshire, to carry out a render and plastering project to their home.

There was a huge crack forming both on the inside and outside of the rear property wall, so we had to inspect this first.



For this project we:

- Erected tower scaffolding.
- Removed the render from the panels at the rear of the property and checked the lintel.
- Removed the kitchen wall unit and plaster around the window.
- Replaced the lintel and altered the pipework.
- Re-plastered the wall and rendered the external panels in EWI silicone cream.
- Removed the skirting, WC frame and the blown/cracked plaster from the walls in the hallway.
- Re-plaster boarded the walls followed by blue grit.
- Skimmed the walls.
- Installed new WC frame and existing door.
- Installed new skirting.
- Cleared site on completion

The project took 4 weeks to complete as we were working alongside a structural engineer.

The clients were so pleased with the finished result and said they would happily recommend us to friends and family.



